Thursday, 14 November 2013 15:48:56

DashBoard Blue English

e K NAGESH (I/C)

rofile Indent Management Tender Management Catalogue Management Payment Reports Contract Management

ction Management

Commercial Bid Item Details

Tender No. : **BBMP/2013-14/EL/WORK_INDENT7886**

Tender Title : Providing timer switches to electrical street light installations at ward no-13

Department : Bruhat Bengaluru Mahanagara Palike

Sl No	Item Code	Item Name	Unit	Quantity	Approved Estimate Price (INR)	Unit Rate(All inclusive)	Amount	Amount In Words	Action
1	04	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	SqCm	45000	0.33	0.27	12150	Twelve Thousand One Hundred and Fifty (dot) Zero Only.	
2	04	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete c) 63 Amps	Each	6	219	178	1068	One Thousand and Sixty Eight (dot) Zero Only.	
3	04	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	6	7515	6118	36708	Thirty Six Thousand Seven Hundred and Eight (dot)	
4	04	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. b) 40-63 Amps SP 1) Group 'A'	Each	6	370	301	1806	One Thousand Eight Hundred and Six (dot) Zero Only.	
5	04	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947. c) 60-70 Amps	Each	6	3865	3146	18876	Eighteen Thousand Eight Hundred and Seventy Six	
6	04	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a) a) 40x40x6mm	Rmtr	10	240	195	1950	One Thousand Nine Hundred and Fifty (dot) Zero Only.	
7	04	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV ClassI. Class 'A' PVC Cable d) 4 core 16sqmm	Per Mtr	55	150	122	6710	Six Thousand Seven Hundred and Ten (dot) Zero Only.	
8	04	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required.II. On wall /Structure a) 6 sqmm to 16sqmm	Rmtr	55	18	15	825	Eight Hundred and Twenty Five (dot) Zero Only.	
9	04	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 16 sqmm	Each	48	14	11.5	552	Five Hundred and Fifty Two (dot) Zero Only.	
10	04	Supplying.....amps rated 3 phase with neutral bus bar using requirement capacity electrolytic aluminium strips covered with heat shrinkable coloured PVC	Rmtr	0.6	1600	1302	781.2	Seven Hundred and Eighty One	

	sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on powder coated 40x6 mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete.100Amps 4x30x6mm Alluminium Strips		(dot) Two Only.

Total Bid Amount (Rs. in figures) : 81426.2

Total Bid Amount (Rs. in words) : Eighty One Thousand Four Hundred and Twenty Six (dot) Two Only.

BACK

This site is best viewed in 1024x768 resolution.